



BILL OF MATERIALS		
MARK #	DESCRIPTION	QTY.
X8080P	(PATTERSON PLASTICS) 3/8" x 6" STRANDED LIFTER W/CONDUIT (PLAIN)	4
REINFORCING SCHEDULE		
MARK #	DESCRIPTION	QTY.
STANDARD PARTS		
CUSTOM PARTS		
MK001	#4 X 8'-9" (PLAIN)	13
MK002	#4 X 7'-9" (PLAIN)	10
MK003	#4 X 5'-0 1/2" (PLAIN)	6
MK004	#4 X 1'-9" (PLAIN)	8
MK005	#4 X 0'-6" (PLAIN)	6
MESH SCHEDULE		
MARK #	DESCRIPTION	QTY.
M1	WWF 4X4-W4XW4 7'-9" X 8'-9" CUT TO FIT	1

HANDLING INSTRUCTIONS

CONCRETE INSTRUCTIONS
 CONCRETE RELEASE @ 2,000 P.S.I.
 CONCRETE @ 28 DAYS: 5,000 P.S.I.
CONCRETE MIXES
 CONCRETE - GRAY VOLUME = 2.37 C.Y.
 CONCRETE - MIX 1 VOLUME = - C.Y.
 CONCRETE - MIX 2 VOLUME = - C.Y.
 SOFT SOUND VOLUME = - C.Y.
 TOTALS VOLUME = 2.37 C.Y.

FINISHING INSTRUCTIONS
 WJ = WET TROWEL
 FF = FORM FINISH

CONCRETE MIXES
 L = 9'-0" SQ.FT.(T.I.F.) =
 W = 8'-0" SQ.FT.(T.I.F.) =
 D = 1'-0" SQ.FT.(T.I.F.) =

CONTROL NUMBERS:
 -

REVISED
 JUL 20 2012
PRINT
 JUL 20 2012
 DESTROY PREVIOUS PRINTS

MESSAGE CENTER

STANDARD PRODUCT

CHECKED BY: *SS/SO* DATE: 7.20.12
 APPROVED BY: DATE: 7.20.12

PRODUCT	SALES ORDER NUMBER
UTILITY PAD	STANDARD
SHEET NUMBER	NUMBER REQUIRED
1 OF 1	1

SMITH-MIDLAND
 PRECAST CONCRETE

P.O. Box 300 Midland, VA 22728
 (540) 439-3266 1(800) 364-3981 FAX (540) 439-1232

DATE	DESCRIPTION	INI.	WCR	A	A	A	A	A
07.20.12	PULLED REBAR DIMENSIONS FROM EDGE OF STEEL	-	-	-	-	-	-	-

PROJECT: UPD189 UTILITY PAD
 5119 CATLETT RD
 MIDLAND VA 22728
 CONTRACTOR: SMITH-MIDLAND CORPORATION

SCALE: NTS
 DRAWN BY: RTH
 ISSUE DATE: 11-04-11
 PIECE MARK: UPD189